## GRAVEL STOP PRINT APPROVAL

ANSI/SPRI ES-1 CERTIFIED -.040" Aluminum = 170 psf, 24GA Steel = 180 psf



	Varies	S - Gravel Stop Gravel Stop Cleat(22GA Galv. Continuous Cleat Roof Membrane Type = Thickness = $1^{\prime\prime}$ $1^{\prime\prime}$ S.S. Ring Shank 12" on Center Through Pre-Punch Hole $1^{\prime\prime}$ S.S. Ring Shank 12" on Center Through Membrane and Pre-Punch Hole
MATERIAL		QUANTITIES
24GA	.040" AL	Lineal Feet (10'-0" Lengths):
22GA	.050" AL	Outside Miters*: Optional Welded (Surcharge Applies)
Other:		Inside Miters*: Optional Welded (Surcharge Applies)
		Right End Caps*: Optional Welded (Surcharge Applies)
Finish:		Left End Caps*: Optional Welded (Surcharge Applies)
Color:		Splice Plate Tape Sealant: Optional Sealant (Surcharge Applies)
		*Standard riveted
PROJECT DETAILS		PRINT APPROVAL
		Architect and/or Contractor shall verify all dimensions, sizes,
		and quantities, All products to be installed in strict accordance
		Effective Date:
		Drawn By:
		Approved By:

1234 Gardiner Lane | Louisville, KY 40213 | drexelmetals.com | 888-321-9630 | Fax: 877-321-9638